Maryland LR Garcia Construction Inc. 3338 Kreitler Rd, Forest Hill, MD 21050

Phone: (410) 793-2611 December 12, 2024


Letter of Explanation


To whom it may concern,


The property, 115 S Jerome Pkwy, Glen Burnie, MD 21060, is 59-ft in length by 30-ft in width, the amount of land that the house covers is 1680-sq ft. The entire area of land is 10606-sq ft. The front of the property is 27-ft from the street, S Jerome Pkwy. There is a garage, shed, and gazebo pre-existing on the property. The dimensions of the gazebo are 9-ft in length by 9-ft in width, 2-ft from the housing unit and 16-ft from the closest property line. The garage is 22-ft in length by 13-ft in width, six-ft from the housing unit and six-ft from the property line. Lastly, the shed is 11-ft in length by 11-ft in width, 40-ft from housing unit and 10-ft from the closest property line. The environment of the housing unit is located in the suburbs, the housing unit is across from trees, the street S Jerome Pkwy in between the trees and house.

Proposed work at this address includes a deck at the front entrance, the deck being 18-ft from the street of S Jerome Pkwy after completion. The dimensions of the deck are 16-ft by 8-ft. The deck shall be built with four 6x6 posts onto concrete footing, deck being framed with pressure-treated wood, composite flooring, vinyl railing, and an onset of stairs that attach to deck and lead to the front entrance of the unit, 115 S Jerome Pkwy. Perimeter of the deck shall be covered with PVC boards. There will be a porch covering on top of deck, spanning 16-ft by 9-ft. The porch will use 6x6 posts and 2x10 beams with 2x6 porch framing along with ½-inch plywood and architectural shingles.

The variance is required due to the setback requirements of the proposed structure needing to be 25-ft from the front property line. Due to the proposed structure being 18-ft from the front property line, a variance is needed to bypass this issue.







SCALE: 1/4" = 1' WHEN PRINTED ON 11x17 PAPER

DISCLAIMER: THIS PLAN IS NOT CONSIDERED COMPLETE UNLESS APPROVED BY YOUR LOCAL BUILDING INSPECTOR OR STRUCTURAL ENGINEER.

BUILDER ACCEPTS ALL RESPONSIBILITY AND LIABILITY.

DECKS.COM LLC, AND ASSOCIATED SPONSORS
ACCEPT NO LIABILITY FOR THE USE OF THIS PLAN.

BASED ON THE INTERNATIONAL RESIDENTIAL CODE

WITH POST BASE HARDWARE STAIRWAY ILLUMINATION: ALL EXTERIOR STAIRWAYS
SHALL BE ILLUMINATED AT THE TOP LANDING TO
THE STAIRWAY, ILLUMINATION SHALL BE CONTROLLED
FROM INSIDE THE DWELLING OR AUTOMATICALLY
ACTIVATED.

RIDGE BOARD
FLASHED AT ROOFING
AND BOLTED TO HOUSE
WITH (1) 1/2" BOLT
EVERY 16" O.C.

HOUSE

ROOF PITCH 3
12

DOFING AT HOUSE CONNECTION AND BOLT RIDGE BOARD WITH (1) 1/2" BOLTS EVERY ARE TO BE HANDERAMED 246 SPF 16" O.C. SPACING S SIDE HANDER BEAM TO BE 2-2210 SPF OR EDUNALENT


16"

SECTION VIEW

4

1PS1610

DISCLAIMER: ONLY USE #2 OR BETTER PRESSURE TREATED
SOUTHERN YELLOW PINE 2 x 10 FOR FRAMING MATERIALS
NEVER SUBSTITUTE COMPOSITE OR SOFTWOODS FOR FRAMING MATERIALS



Maryland LR Garcia Construction

Contract

3338 Kreitler Rd, Forest Hill, MD 21050 (410) 793-2611 mdlrgarciainc@gmail.com

To: Robert Danowski 115 S Jerome Pkwy Glen Burnie, MD 21060 Date: 11-03-2024

Description	Line total
This includes building the deck 16-ft x 8-ft with four 6x6 posts on to concrete footing, deck framed with pressure treated lumber, composite flooring, vinyl railing, onset of stairs on front of deck as shown in picture attached with porch all across deck, porch will be 16x9 with 6x6 posts and 2x10 beams with 2x6 porch framing and half-inch plywood with architectural shingles. Porch will be open, beam and post of porch will be wrapped in PVC, perimeter of deck will be covered with PVC Boards,	22750.00
* deck board color: untique leather Down Payment	22750.00
Down Payment	7507.50
20) Wiliam (00)	7621.25
* Crown railing Cap Second Payment * white viryl railing Third Payment	

Down payment is used for purchasing the material for the project.

Second payment due upon 50% completion

Third and final payment is due at the completion of the project after inspection with homeowner

Contract prepared by: Elder Estrada

To accept contract, sign below: